


Mayor  
S. Scott Vandergrift

City Manager  
Robert Frank



Commissioners  
Gary Hood, District 1  
Scott Anderson, District 2  
Rusty Johnson, District 3  
Joel F. Keller, District 4

## **AS-BUILT INFORMATION**

As-built drawings will be required with the following information:

### **SANITARY SEWER**

- a. Top elevation of each manhole frame & cover.
- b. Invert of each line entering and leaving each manhole/structure.
- c. Length of each run of main between manholes (center to center).
- d. Actual grade of pipe between manholes.
- e. Locate all service wyes from downstream manhole with depth at lot line, and distance from main line.
- f. Locate with measurements from permanent visible objects all fittings/accessories not visible from the surface (min.2 Pt.ties).

### **STORM DRAINAGE**

- a. Top elevation of each manhole frame & cover/grate as well as all other structures (headwalls, control structures, etc.)
- b. Invert elevation of each line entering and leaving each structure, including underdrain pipes.
- c. Inverts of all mitered end sections.
- d. Actual grade of the pipe between the structures.
- e. Invert elevation & 2 horizontal ties from permanent visible objects to all storm stubouts.

### **WATER SYSTEM AND FORCEMAINS**

- a. Actual lengths of pipe between branches & valves in the run.
- b. Locate with measurements from permanent visible objects all fittings/accessories not visible from the surface (min.2. Pt.ties).
- c. List the depth of the lines at all valves fittings and fire hydrants.

Until "FINAL AS-BUILT" drawings are submitted to the City of Ocoee Utilities/Engineering Department for approval, the developer nor the contractor will not receive a Temporary Certificate of Occupancy or a Certificate of Occupancy. **NO EXCEPTIONS**